

ROUTE 25 & OAK HILL ROAD IMPROVEMENT PROJECTS

INTERSECTION RECONSTRUCTION, SIDEWALKS & ROAD CONSTRUCTION
ROUTE 25 & OAK HILL ROAD
STANDISH, MAINE

For
TOWN OF STANDISH
175 NORTHEAST ROAD
STANDISH, MAINE 04084

PROJECT A - CONNECTOR ROAD, ROUTE 25 & OAK HILL ROAD INTERSECTION IMPROVEMENTS
PROJECT B - ROUTE 25 SIDEWALK IMPROVEMENTS



MAY 2012

PLAN INDEX		PROJECT
1	MASTER PLAN	A & B
2	EXISTING CONDITIONS, REMOVALS AND DEMOLITION PLAN	A & B
3	LAYOUT PLAN	A & B
4	CONNECTOR ROAD PLAN AND PROFILE	A
5	OAK HILL ROAD PLAN AND PROFILES & INTERSECTION RECONSTRUCTION	A
6	ROUTE 25 PLAN	B
7	EROSION CONTROL PLAN & DETAILS	A & B
8	ROADWAY DETAILS	A & B
9	STANDARD DETAILS	A & B




Berry, Huff, McDonald, Milligan Inc.
Engineers, Surveyors

28 State Street
Gorham, Maine 04038
Tel. (207) 839-2771
Fax (207) 839-8250



DESIGN PLAN SUMMARY	
DESIGN ITEMS	PLAN
1. EXISTING CONDITIONS, DEMOLITION & REMOVALS	SHEET 2
2. PROJECT LAYOUT, DIMENSIONS & ORIENTATION	SHEET 3
3. GRADING, STORWATER, EROSION CONTROL, PLAN AND PROFILES AND GENERAL DESIGN INFORMATION	SHEET 4

REVISION	
NO.	DATE



BH2M


Berry, Huff, McDonald, Milligan Inc.
Engineers, Surveyors

28 State Street
Coffman, Maine 04038
Tel. (207) 859-2771
Fax (207) 859-8250


FOR
The Town of Standish
175 Northeast Road
Standish, Maine 04084

MASTER PLAN
ROUTE 25 & OAK HILL ROAD
IMPROVEMENT PROJECTS
ROUTE 25 AND OAK HILL ROAD
STANDISH, MAINE

DESIGNED W. Polkey	DATE Jan. 2012
DRAWN Dept.	SCALE As Noted
CHECKED L. Berry	JOB. NO. 11107



DESIGNED W. Pelkey	DATE Jan. 2012
DRAWN Dept.	SCALE As Noted
CHECKED L. Berry	JOB. NO. 11107



EASEMENT LINE DATA

- E1 - 40.00'
- E2 - 22.00'
- E3 - 40.00'
- E4 - 22.00'
- E5 - 22.00'
- E6 - 20.00'
- E7 - 50.10'
- E8 - 20.00'
- E9 - 20.00'
- E10 - 39.06'
- E11 - 7.02'
- E12 - 41.17'

ROAD LINE DATA

- L1 - S55°56'22"E 20.56'
- L2 - S01°34'49"E 32.00'
- L3 - N04°36'47"W 24.65'
- L4 - N36°24'38"E 200.54'
- L5 - N57°04'31"W 22.66'
- L6 - N89°07'35"E 59.70'
- L7 - S55°56'22"E 18.36'

Q CURVE DATA

- CURVE #1
 - R=50.00'
 - L=47.44'
 - T=25.67'
 - D=54°21'34"
 - PC=0+32.01
 - PT=0+79.45
- CURVE #2
 - R=150.00'
 - L=107.40'
 - T=56.12'
 - D=41°01'25"
 - PC=0+24.65
 - PT=1+32.05
- CURVE #3
 - R=150.00'
 - L=244.75'
 - T=159.42'
 - D=93°29'00"
 - PC=3+32.59
 - PT=5+77.34
- CURVE #4
 - R=200.00'
 - L=121.94'
 - T=62.93'
 - D=34°56'03"
 - PC=0+59.70
 - PT=1+81.64

REVISION		DESCRIPTION
NO.	DATE	

BH2M

Berry, Huff, McDonald, Milligan Inc.
Engineers, Surveyors

Tel. (207) 859-2771
Fax (207) 859-8250

28 State Street
Coffman, Maine 04038


FOR
The Town of Standish
175 Northeast Road
Standish, Maine 04084

LAYOUT PLAN
ROUTE 25 & OAK HILL ROAD
IMPROVEMENT PROJECTS
ROUTE 25 AND OAK HILL ROAD
STANDISH, MAINE

DESIGNED W. Polkey	DATE Jan. 2012
DRAWN Dept.	SCALE As Noted
CHECKED L. Berry	JOB. NO. 11107

SHEET
3


REPRODUCTION OR REUSE OF THIS DOCUMENT WITHOUT THE EXPRESSED WRITTEN CONSENT OF BH2M INC. IS PROHIBITED



STORMDRAIN PIPES	
SD1 - 15" S.D., L=55', S=0.005'/FT.	
SD2 - 15" S.D., L=39', S=0.022'/FT.	
SD3 - 15" S.D., L=45', S=0.030'/FT.	
SD4 - 15" S.D., L=41', S=0.030'/FT.	
SD5 - 18" S.D., L=45', S=0.050'/FT.	
SD6 - 18" S.D., L=49', S=0.005'/FT.	

STORMDRAIN STRUCTURES	
CB#1	RIM 419.24 15" INV. OUT 415.49
CB#2	RIM 416.44 15" INV. OUT 412.69
CB#3	RIM 415.59 15" INV. IN 411.83 15" INV. OUT 411.73
CB#4	RIM 414.45 15" INV. IN 410.38 15" INV. OUT 410.28
DMH#1	RIM 413.28 15" INV. IN 409.05 18" INV. IN 409.05 18" INV. OUT 408.95


HIGH POINT ELEV = 419.99
HIGH POINT STA = 0+83.35
PVI STA = 1+00
PVI ELEV = 420.16
A.D. = -1.50
K = 66.70



PVI STA = 3+75
PVI ELEV = 417.41
A.D. = -3.34
K = 31.39

PVI STA = 5+00
PVI ELEV = 411.98
A.D. = 3.84
K = 35.13

- NOTES:
1. INSTALL LOWPOINT SEDIMENT CONTROL BARRIERS AT ALL CATCH BASIN LOCATIONS, SEE DETAIL.
 2. CONDUITS FOR POWER AND COMMUNICATION CABLES SHALL BE SPECIFIED BY APPROPRIATE UTILITY COMPANIES.
 3. MINIMUM 1' VERTICAL CLEARANCE BETWEEN WATER SERVICE CROSSINGS AND SEWER MAIN/SERVICES. MINIMUM 6" CLEARANCE FROM STORM DRAIN CROSSINGS.
 4. INSTALL STABILIZED CONSTRUCTION ENTRANCE PRIOR TO CONSTRUCTION, SEE DETAIL.
 5. BENCHMARK: 4" NAIL IN UP 9 ALONG ROUTE 25
ELEVATION=420.83 (NGVD88)
BASED ON MDOT DISC TT 13 BT 1940
SET IN NORTHEAST CORNER OF ROUTE 25/35



PROFILE
SCALE
VERTICAL: 1" = 5'
HORIZONTAL: 1" = 25'

LEGEND	
---	WATER SERVICE
---	SANITARY SEWER
---	UNDERGROUND ELECTRIC
---	STORM DRAIN
---	PRESSURE SEWER
---	SILT FENCE
---	EXISTING CONTOUR
---	PROPOSED CONTOUR
---	TRANSFORMER PAD
---	UTILITY POLE
---	SANITARY SEWER MANHOLE
---	CATCH BASIN
---	DRAIN MANHOLE
---	STREET LIGHT

REVISION	
NO.	DESCRIPTION

BH2M
Berry, Huff, McDonald, Milligan Inc.
Engineers, Surveyors
28 State Street
Cottam, Maine 04038
Tel. (207) 859-2771
Fax (207) 859-8250





FOR
The Town of Standish
175 Northeast Road
Standish, Maine 04084

CONNECTOR ROAD
PLAN & PROFILE
PROJECT A
ROUTE 25 & OAK HILL ROAD
IMPROVEMENT PROJECTS
ROUTE 25 AND OAK HILL ROAD
STANDISH, MAINE

DESIGNED W. Pelkey	DATE Jan. 2012
DRAWN Dept.	SCALE As Noted
CHECKED L. Berry	JOB. NO. 11107


SHEET 4

REPRODUCTION OR REUSE OF THIS DOCUMENT WITHOUT THE EXPRESSED WRITTEN CONSENT OF BH2M INC. IS PROHIBITED



REPRODUCTION OR REUSE OF THIS
DOCUMENT WITHOUT THE
EXPRESSED WRITTEN CONSENT
OF BH2M INC. IS PROHIBITED

\\server\csp\2011\1107_data\Profile P_data_5/10/2012 2:22:11 PM



EXISTING STORMDRAIN STRUCTURES

DMH 1	RIM 415.20
	INV. IN (12" PE)=409.56
	INV. OUT (15" RCP)=409.56
CB 1	RIM 429.40
	INV. IN (6" UD)=424.10±
	INV. OUT (12" PE)=424.10
CB 2	RIM 418.61
	INV. IN (12" PE)=413.96±
	INV. OUT (15" RCP)=413.96
CB 3	RIM 418.69
	INV. IN (15" RCP)=413.84±
	INV. IN (24" PE)=413.84±
CB 4	RIM 421.84
	INV. IN (12" PE)=416.59
	INV. IN (24" PE)=416.59
CB 5	RIM 419.91
	INV. OUT (15" PE)=416.91±
CB 6	RIM 416.42
	INV. IN (18" PE)=411.54
CB 7	RIM 415.93
	INV. IN (24" PE)=410.69
	INV. OUT (24" PE)=410.59
CB 8	RIM 414.70
	INV. IN (18" PE)=409.58
	INV. OUT (18" PE)=409.53
CB 9	RIM 414.60
	INV. IN (24" PE)=409.00
	INV. OUT (15" PE)=409.00
CB 10	RIM 414.01
	INV. OUT (12" PE)=410.31

- NOTES:
1. INSTALL LOWPOINT SEDIMENT CONTROL BARRIERS AT ALL CATCH BASIN LOCATIONS, SEE DETAIL.
 2. CONDUITS FOR POWER AND COMMUNICATION CABLES SHALL BE SPECIFIED BY APPROPRIATE UTILITY COMPANIES.
 3. MINIMUM 1' VERTICAL CLEARANCE BETWEEN WATER SERVICE CROSSINGS AND SEWER MAIN/SERVICES. MINIMUM 6" CLEARANCE FROM STORM DRAIN CROSSINGS.
 4. INSTALL STABILIZED CONSTRUCTION ENTRANCE PRIOR TO CONSTRUCTION, SEE DETAIL.
 5. BENCHMARK: 4" NAIL IN UP 9 ALONG ROUTE 25 ELEVATION=420.83 (NGVD88) BASED ON MDOT DISC TT 13 BT 1940 SET IN NORTHEAST CORNER OF ROUTE 25/35

STORMDRAIN PIPES


SD1 - 15" S.D., L=55', S=0.005'/FT.
SD7 - 15" S.D., L=30', S=0.057'/FT.
SD8 - 15" S.D., L=133', S=0.0071'/FT.
SD9 - 18" S.D., L=53', S=0.045'/FT.

STORMDRAIN STRUCTURES

CB#1	RIM 419.24
	15" INV. OUT 415.49
CB#5	RIM 419.70
	15" INV. OUT 415.95
CB#6	RIM 418.00
	15" INV. IN 414.24
	15" INV. OUT 414.14

LEGEND	
---	WATER SERVICE
---	SANITARY SEWER
---	UNDERGROUND ELECTRIC
---	STORM DRAIN
---	PRESSURE SEWER
---	SILT FENCE
---	EXISTING CONTOUR
---	PROPOSED CONTOUR
---	TRANSFORMER PAD
---	UTILITY POLE
---	SANITARY SEWER MANHOLE
---	CATCH BASIN
---	DRAIN MANHOLE
---	STREET LIGHT

REVISION	
NO.	DATE



BH2M

Berry, Huff, McDonald, Milligan Inc.
Engineers, Surveyors

Tel. (207) 859-2771
Fax (207) 859-8250

28 State Street
Columbia, Maine 04008

FOR
The Town Of Standish
175 Northeast Road
Standish, Maine 04084

ROUTE 25 PLAN
PROJECT B
ROUTE 25 & OAK HILL ROAD
IMPROVEMENT PROJECTS
ROUTE 25 AND OAK HILL ROAD
STANDISH, MAINE

DESIGNED W. Pelkey	DATE Jan. 2012
DRAWN Dept.	SCALE As Noted
CHECKED L. Berry	JOB. NO. 11107

SHEET
6

REPRODUCTION OR REUSE OF THIS DOCUMENT WITHOUT THE EXPRESSED WRITTEN CONSENT OF BH2M INC. IS PROHIBITED

\\laser\cadd\2024\1007\Main\Erosion Stabilization 5/10/2024 03:52 AM

EROSION AND SEDIMENT CONTROL PLAN
THIS PLAN HAS BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE STANDARDS AND SPECIFICATIONS FOR EROSION PREVENTION IN DEVELOPING AREAS AS CONTAINED IN THE "MAINE EROSION AND SEDIMENT CONTROL BMP'S", DEPARTMENT OF ENVIRONMENTAL PROTECTION DATED MARCH 2003. FOR ADDITIONAL DETAILS AND SPECIFICATIONS SEE BMP'S MANUAL.

THE PROPOSED LOCATIONS OF SILTATION AND EROSION CONTROL STRUCTURES ARE SHOWN ON THE SITE PLAN.

- ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE DONE IN ACCORDANCE WITH THE "MAINE EROSION AND SEDIMENT CONTROL BMP'S", DEPARTMENT OF ENVIRONMENTAL PROTECTION, DATED MARCH 2003.
- THOSE AREAS UNDERGOING ACTUAL CONSTRUCTION WILL BE LEFT IN AN UNTREATED OR UNVEGETATED CONDITION FOR A MINIMUM TIME. AREAS SHALL BE PERMANENTLY STABILIZED WITHIN 7 DAYS OF FINAL GRADING AND TEMPORARILY STABILIZED WITHIN 7 DAYS OF INITIAL DISTURBANCE OF THE SOIL. IF THE DISTURBANCE IS WITHIN 100 FEET OF A STREAM OR POND, THE AREA SHALL BE STABILIZED WITHIN 2 DAYS OR PRIOR TO ANY STORM EVENT (THIS WOULD INCLUDE WETLANDS).
- SEDIMENT BARRIERS (EROSION CONTROL MIX, STONE CHECK DAMS, STABILIZED CONSTRUCTION ENTRANCE, ETC.) SHOULD BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF THE CONTRIBUTING DRAINAGE AREA ABOVE THEM.
- INSTALL EROSION CONTROL MIX AT TOE OF SLOPES TO FILTER SILT FROM RUNOFF. SEE E.C. MIX DETAIL FOR PROPER INSTALLATION. EROSION CONTROL MIX WILL REMAIN IN PLACE PER NOTE #6.
- ALL EROSION CONTROL STRUCTURES WILL BE INSPECTED, REPLACED AND/OR REPAIRED EVERY 7 DAYS AND IMMEDIATELY BEFORE AND FOLLOWING ANY SIGNIFICANT RAINFALL (0.5 INCHES) OR SNOW MELT OR WHEN NO LONGER SERVICEABLE DUE TO SEDIMENT ACCUMULATION OR DECOMPOSITION. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPLOUSE ARE STABILIZED BY TURF. EROSION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS OF PERMANENT STABILIZATION. PERMANENT STABILIZATION IS 90% GRASS CATCH IN VEGETATED AREAS.
- NO SLOPES, EITHER PERMANENT OR TEMPORARY, SHALL BE STEEPER THAN TWO TO ONE (2 TO 1).
- IF FINAL SEEDING OF THE DISTURBED AREAS IS NOT COMPLETED 45 DAYS PRIOR TO THE FIRST KILLING FROST, USE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS WELL) TO PROTECT THE SITE AND DELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD.
- TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINAL GRADED SHALL BE COMPLETED BY AUG. 15 OR 45 DAYS PRIOR TO THE FIRST KILLING FROST (OCT. 1) TO PROTECT FROM SPRING RUNOFF PROBLEMS.
- DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT WILL BE RETURNED TO THE SITE AND REGRADDED ONTO OPEN AREAS. POST SEEDING SEDIMENT, IF ANY, WILL BE DISPOSED OF IN AN ACCEPTABLE MANNER.
- REVEGETATION MEASURES WILL COMMENCE UPON COMPLETION OF CONSTRUCTION EXCEPT AS NOTED ABOVE. ALL DISTURBED AREAS NOT OTHERWISE STABILIZED WILL BE GRADED, SMOOTHED, AND PREPARED FOR FINAL SEEDING AS FOLLOWS:
 - FOUR INCHES OF LOAM WILL BE SPREAD OVER DISTURBED AREAS AND SMOOTHED TO A UNIFORM SURFACE.
 - APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL, FERTILIZER MAY BE APPLIED AT THE RATE OF 800 POUNDS PER ACRE OR 18.4 POUNDS PER 1,000 SQUARE FEET USING 10-20-20 (N-P20S-K20) OR EQUIVALENT. APPLY GROUND LIMESTONE (EQUIVALENT TO 50% CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE (138 LBS PER 1,000 SQ. FT.).
 - FOLLOWING SEED BED PREPARATION, DITCHES AND BACK SLOPES WILL BE SEED TO A MIXTURE OF 47% CREEPING RED FESCUE, 5% REDTOP, AND 48% TALL FESCUE. THE LAWN AREAS WILL BE SEED TO A PREMIUM TURF MIXTURE OF 44% KENTUCKY BLUEGRASS, 44% CREEPING RED FESCUE, AND 12% PERENNIAL RYEGRASS. SEEDING RATE IS 1.03 LBS PER 1,000 SQ. FT. LAWN QUALITY SOD MAY BE SUBSTITUTED FOR SEED. SEED MIX SHALL CONTAIN 10% ANNUAL RYE GRASS.
 - HAY MULCH AT THE RATE OF 70-90 LBS PER 1,000 SQUARE FEET OR A HYDRO-APPLICATION OF ASPHALT, WOOD OR PAPER FIBER SHALL BE APPLIED FOLLOWING SEEDING. A SUITABLE BINDER SUCH AS CURASOL OR RMB PLUS WILL BE USED ON HAY MULCH FOR WIND CONTROL.
- ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS ONCE THE SITE IS STABILIZED WITH 90% GRASS CATCH IN VEGETATED AREAS. TEMPORARY EROSION AND SEDIMENT CONTROL BLANKET SHALL BE USED IN ALL DITCHES AND SWALES AS SHOWN IN DETAILS.
- WETLANDS WILL BE PROTECTED WITH EROSION CONTROL MIX OR SILT FENCE INSTALLED AT THE EDGE OF THE WETLAND OR THE BOUNDARY OF WETLAND DISTURBANCE.

MULCH AND MULCH ANCHORING

MULCH

LOCATION	MULCH	RATE (1000 S.F.)
PROTECTED AREA	STRAW OR HAY *	100 POUNDS
WINDY AREAS	SHREDDED OR CHOPPED CORNSTALKS STRAW OR HAY (ANCHORED) *	185-275 POUNDS 100 POUNDS
MODERATE TO HIGH VELOCITY AREAS OR STEEP SLOPES (GREATER THAN OR EQUAL TO 3:1)	JUTE MESH OR EXCELISOR MAT	AS REQUIRED AS REQUIRED

(GREATER THAN OR EQUAL TO 3:1)
* A HYDRO-APPLICATION OF ASPHALT, WOOD, OR PAPER FIBER MAY BE APPLIED FOLLOWING SEEDING. A SUITABLE BINDER SUCH AS CURASOL OR RMB PLUS SHALL BE USED ON HAY MULCH FOR WIND CONTROL.


MULCH ANCHORING

ANCHOR MULCH WITH PEG AND TWINE (1 SQ. YD./BLOCK); MULCH NETTING (AS PER MANUFACTURER); ASPHALT EMULSION (0.04 GALLONS PER SQ. YD.); LIQUID ASPHALT (0.10 GALLONS PER SQ. YD.); WOOD CELLULOSE FIBER (750 LBS/ACRE); CHEMICAL TACK (AS PER MANUFACTURER SPECIFICATIONS); USE OF A SERRATED STRAIGHT DISK. NETTING FOR SMALL AREAS AND ROAD DITCHES MAY BE PERMITTED.

Additional temporary seed mixture (for periods less than 12 months).

Season	Seed	Rate
Summer (5/15 - 8/15)	Sudangrass Oats	40 lbs/acre 80 lbs/acre
Late Summer/Early Fall (8/15 - 9/15)	Perennial Ryegrass	40 lbs/acre
Fall (9/15 - 11/1)	Winter Rye	112 lbs/acre
Winter (11/1 - 4/1)	Mulch w/ Dormant Seed	80 lbs/acre*
Spring (4/1 - 7/1)	Oats Annual Ryegrass	80 lbs/acre 40 lbs/acre

*Seed Rate Only








EROSION CONTROL DURING CONSTRUCTION

WINTER CONSTRUCTION

- WINTER CONSTRUCTION PERIOD: OCTOBER 1 THROUGH APRIL 15
- WINTER EXCAVATION AND EARTHWORK SHALL BE DONE SUCH THAT NO MORE THAN 1 ACRES OF THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME.
- EXPOSED AREA SHOULD BE LIMITED TO THAT WHICH CAN BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT.
- CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED SUCH THAT NO MORE THAN ONE ACRE OF THE SITE IS WITHOUT EROSION CONTROL PROTECTION.
- OVERWINTER STABILIZATION OF DITCHES AND CHANNELS:
ALL STONE-LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED AND STABILIZED BY NOVEMBER 15. ALL GRASS LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED AND STABILIZED BY SEPTEMBER 1. IF A DITCH OR CHANNEL IS NOT GRASS-LINED BY SEPTEMBER 1, THEN ONE OF THE FOLLOWING ACTIONS MUST BE TAKEN TO STABILIZE THE DITCH FOR LATE FALL AND WINTER.
 - INSTALL A SOD LINING IN THE DITCH:
A DITCH MUST BE LINED WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES: PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL, AND ANCHORING SOD AT THE BASE OF THE DITCH WITH JUTE OR PLASTIC MESH TO PREVENT THE SOD FROM SLOUGHING DURING FLOW CONDITIONS. SEE THE PERMANENT VEGETATION BMP SECTION.
 - INSTALL A STONE LINING IN THE DITCH:
A DITCH MUST BE LINED WITH STONE RIPRAP BY NOVEMBER 15. A REGISTERED PROFESSIONAL ENGINEER MUST BE HIRED TO DETERMINE THE STONE SIZE AND LINING THICKNESS NEEDED TO WITHSTAND THE ANTICIPATED FLOW VELOCITIES AND FLOW DEPTHS WITHIN THE DITCH. IF NECESSARY, THE CONTRACTOR WILL REGRADE THE DITCH PRIOR TO PLACING THE STONE LINING SO TO PREVENT THE STONE LINING FROM REDUCING THE DITCH'S CROSS-SECTIONAL AREA.
- OVERWINTER STABILIZATION OF DISTURBED SLOPES:
ALL STONE-COVERED SLOPES MUST BE CONSTRUCTED AND STABILIZED BY NOVEMBER 15. ALL SLOPES TO BE VEGETATED MUST BE SEEDED AND MULCHED BY SEPTEMBER 1. THE DEPARTMENT WILL CONSIDER ANY AREA HAVING A GRADE GREATER THAN 15% TO BE A SLOPE. IF A SLOPE IS TO BE VEGETATED IS NOT STABILIZED BY SEPTEMBER 1, THEN ONE OF THE FOLLOWING ACTIONS MUST BE TAKEN TO STABILIZE THE SLOPE FOR LATE FALL AND WINTER:
 - STABILIZE THE SOIL WITH TEMPORARY VEGETATION:
BY OCTOBER 1, SEED THE DISTURBED SOIL WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET, LIGHTLY MULCH THE SEEDED SOIL WITH HAY OR STRAW AT 75 POUNDS PER 1000 SQUARE FEET, AND ANCHOR THE MULCH WITH PLASTIC NETTING. MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR FAILS TO COVER AT LEAST 75% OF THE DISTURBED SOIL BEFORE NOVEMBER 1, THEN MULCH THE AREA FOR OVER-WINTER PROTECTION AS DESCRIBED BELOW.
 - STABILIZE THE SOIL WITH SOD:
THE DISTURBED SLOPE MUST BE STABILIZED WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES THE CONTRACTOR PINNING THE SOD ONTO THE SLOPE WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. THE CONTRACTOR WILL NOT USE LATE SEASON SOD INSTALLATION TO STABILIZE SLOPES HAVING A GRADE GREATER THAN 33% (3H:1V) OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE. SEE THE TEMPORARY MULCHING BMP SECTION.
 - STABILIZE THE SOIL WITH STONE RIPRAP:
PLACE A LAYER OF STONE RIPRAP ON THE SLOPE BY NOVEMBER 15. THE DEVELOPMENT'S OWNER WILL HIRE A REGISTERED PROFESSIONAL ENGINEER TO DETERMINE THE STONE SIZE NEEDED FOR STABILITY ON THE SLOPE AND TO DESIGN A FILTER LAYER FOR UNDERNEATH THE RIPRAP. SEE THE RIPRAP SLOPE STABILIZATION BMP SECTION.
- OVERWINTER STABILIZATION OF DISTURBED SOILS:
BY SEPTEMBER 15, ALL DISTURBED SOILS ON AREAS HAVING A SLOPE LESS THAN 15% MUST BE SEEDED AND MULCHED. IF THE DISTURBED AREAS ARE NOT STABILIZED BY THIS DATE, THEN ONE OF THE FOLLOWING ACTIONS MUST BE TAKEN TO STABILIZE THE SOIL FOR LATE FALL AND WINTER.
 - STABILIZE THE SOIL WITH TEMPORARY VEGETATION:
BY OCTOBER 1, SEED THE DISTURBED SOIL WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET, LIGHTLY MULCH THE SEEDED SOIL WITH HAY OR STRAW AT 75 POUNDS PER 1000 SQUARE FEET, AND ANCHOR THE MULCH WITH PLASTIC NETTING. MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR FAILS TO COVER AT LEAST 75% OF THE DISTURBED SOIL BEFORE NOVEMBER 1, THEN MULCH THE AREA FOR OVER-WINTER PROTECTION AS DESCRIBED BELOW.
 - STABILIZE THE SOIL WITH SOD:
THE DISTURBED SLOPE MUST BE STABILIZED WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL.
 - STABILIZE THE SOIL WITH MULCH:
BY NOVEMBER 15, MULCH THE DISTURBED SOIL BY SPREADING HAY OR STRAW AT A RATE OF AT LEAST 150 POUNDS PER 1000 SQUARE FEET ON THE AREA SO THAT NO SOIL IS VISIBLE THROUGH THE MULCH. IMMEDIATELY AFTER APPLYING THE MULCH, ANCHOR THE MULCH WITH PLASTIC NETTING TO PREVENT WIND FROM MOVING THE MULCH OFF THE DISTURBED SOIL.
- MAINTENANCE:
MAINTENANCE MEASURES SHALL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION SEASON. AFTER EACH RAINFALL, SNOW STORM OR PERIOD OF THAWING AND RUNOFF, THE SITE CONTRACTOR SHALL PERFORM A VISUAL INSPECTION OF ALL INSTALLED EROSION CONTROL MEASURES AND PERFORM REPAIRS AS NEEDED TO INSURE THE CONTINUOUS FUNCTION. FOLLOWING THE TEMPORARY AND/OR FINAL SEEDING AND MULCHING, THE CONTRACTOR SHALL, IN THE SPRING, INSPECT AND REPAIR ANY DAMAGES AND/OR BARE SPOTS. AN ESTABLISHED VEGETATIVE COVER MEANS A MINIMUM OF 65 TO 80% OF AREAS VEGETATED WITH VIGOROUS GROWTH.


STABILIZATION SCHEDULE BEFORE WINTER:

- | | |
|--|--|
| SEPTEMBER 15 | ALL DISTURBED AREAS MUST BE SEEDED AND MULCHED. ALL SLOPES MUST BE STABILIZED, SEEDED AND MULCHED. ALL GRASS LINED DITCHES AND CHANNELS MUST BE STABILIZED WITH MULCH OR AN EROSION CONTROL BLANKET. |
| OCTOBER 1 | IF THE SLOPE IS STABILIZED WITH AN EROSION CONTROL BLANKET AND SEEDED, ALL DISTURBED AREAS TO BE PROTECTED WITH AN ANNUAL GRASS MUST BE SEED AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET AND MULCHED. |
| NOVEMBER 15 | ALL STONE LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED AND STABILIZED. SLOPES THAT ARE COVERED WITH RIPRAP MUST BE CONSTRUCTED BY THAT DATE. |
| 9. DURING WINTER CONSTRUCTION PERIOD | ALL SNOW SHALL BE REMOVED FROM AREAS OF SEEDING AND MULCHING PRIOR TO PLACEMENT. |
| 10. AREAS WITHIN 100 FEET OF STREAMS THAT ARE NOT STABILIZED WITH VEGETATION BY DEC. 1 | SHALL BE MULCHED AND ANCHORED WITH NETTING. IF WORK CONTINUES IN THIS AREA DURING THE WINTER, A DOUBLE LINE OF SEDIMENT BARRIERS MUST BE USED. |




NOTES:

- CONSULT WITH IF&W IF FISH PASSAGE WILL BE INHIBITED DURING LONG FLOWS.
- REFER TO DESIGN NOTES AND LIMITATIONS IN TEXT NO PIPE OUTLET PROTECTION.
- IN DEFINED CHANNELS, APRON SHALL EXTEND FULL WIDTH OF BOTTOM AND ONE FOOT ABOVE MAX. TAILWATER OR UP TO BANK FULL, WHICHEVER IS LESS.



- Prepare soil before installing blankets, including lime, fertilizer & seed.
- Begin at top of slope by anchoring blanket in 6" x 6" trench. Backfill & compact trench after stapling.
- Roll blankets down or horizontally across slope.
- The edges of parallel blankets must be stapled with approx. 2" overlap.
- When blankets must be spliced down the slope, place blankets end over end (single style) with approx. 4" overlap. Staple through overlapped area, approx. 12" apart.



REVISION	DESCRIPTION
NO.	DATE

NO.	DATE
-----	------

BH2M

Berry, Huff, McDonald, Milligan Inc.
Engineers, Surveyors

Tel. (207) 859-2771
Fax (207) 859-4250

28 State Street
Condom, Maine 04038

FOR
The Town Of Standish
175 Northeast Road
Standish, Maine 04084

EROSION CONTROL PLAN & DETAILS

ROUTE 25 & OAK HILL ROAD IMPROVEMENT PROJECTS

ROUTE 25 AND OAK HILL ROAD
STANDISH, MAINE


DESIGNED W. Polkey	DATE Jan. 2012
DRAWN Dept.	SCALE As Noted
CHECKED L. Berry	JOB. NO. 11107

SHEET
7

REPRODUCTION OR REUSE OF THIS DOCUMENT WITHOUT THE EXPRESSED WRITTEN CONSENT OF BH2M INC. IS PROHIBITED



1. REFERENCE IS MADE TO ACI MANUAL OF PRACTICE, 2010 FOR SPECIFICATIONS AND PRACTICES.
2. CONCRETE: 4,000 PSI @ 28 DAYS
3/4" MAXIMUM AGGREGATE SIZE
AIR ENTRAINMENT 3-5%
SLUMP 4" MAX.
3. REINFORCEMENT: WELDED WIRE MESH, EPOXY COATED 6X6 6/6 HEAVY GAUGE SHEET DISCONTINUED THROUGH JOINTS
4. FINISH: SCREED AND BULL FLOAT, BROOM FINISH
5. JOINTS: SAWCUT JOINTS TO 1/3" DEPTH WITHIN 24 HOURS OF PLACEMENT
PROVIDE AT 5' ON CENTER MINIMUM
EXPANSION JOINTS TO FULL DEPTH OF CONCRETE SLAB WITH JOINT FILLER
PROVIDE AT 25' ON CENTER MINIMUM DISTANCE AND AT ALL APPROPRIATE CONNECTIONS SUCH AS WITH CURBS, BUILDINGS, STAIRS OR ANY OTHER STRUCTURES
6. CURING: APPLY APPROVED CURING COMPOUND
7. SEALING: APPLY SALTGUARD WB WHITE LIQUID SEALANT OR EQUIVALENT PER MANUFACTURES SPECIFICATIONS



THE PAVEMENT SHALL BE THOROUGHLY CLEANED TO REMOVE DUST, DIRT AND OIL BEFORE APPROVED ADHESIVE IS APPLIED PER MANUFACTURERS SPECIFICATIONS.


THE FIBER REINFORCED MIX SHALL BE FED INTO THE VIBRATING HOPPER WHERE IT IS COMPACTED INTO THE DESIRED MOLD PROFILE.

FRESHLY EXTRUDED CURB SHALL BE LIGHTLY TOUCHED UP WITH A STEEL HAND TROWEL. CONTROL JOINTS SHALL BE TOOLED AS SOON AS POSSIBLE AT 9' INTERVALS. ADDITIONAL CONTROL JOINTS ADDED ON RADIUS AS NECESSARY.

THE FINISHED CURB WILL BE COATED WITH AN APPROVED CURING COMPOUND.

FOLLOW MANUFACTURERS INSTALLATION INSTRUCTIONS AND TEMPERATURE RESTRICTIONS.

EXTRUDED CONCRETE CURB
NTS



PAVEMENT JOINT DETAIL

N.T.S.



NOTE:

1. CURB RAMP LENGTHS ARE BASED ON SEVEN AND ONE HALF (7.5) INCH CURB REVEAL HEIGHT AND NO RUNNING SLOPE. RAMP LENGTHS SHALL BE ADJUSTED AS NECESSARY TO ACCOMMODATE VARYING CURB REVEAL HEIGHT AND TO MATCH ADJACENT SLOPES. ADJACENT SIDEWALKS AND SIDEWALK SLOPES TO MAINTAIN A RAMP THAT DOES NOT EXCEED THE MAXIMUM RAMP SLOPE OF 1:12.
2. DETECTABLE WARNINGS SHALL CONSIST OF RAISED TRUNCATED DOMES AND SHALL HAVE A BASE DIAMETER OF 0.9 INCHES (23 mm) MINIMUM AND 1.4 INCHES (36 mm) MAXIMUM; A TOP DIAMETER OF 50 PERCENT OF THE BASE DIAMETER MINIMUM TO 65 PERCENT OF THE BASE DIAMETER MAXIMUM; AND A HEIGHT OF 0.2 INCHES (5.1 mm), A CENTER-TO-CENTER SPACING OF 1.6 INCHES (41mm) MINIMUM AND 2.4 INCHES (61mm) MAXIMUM; AND A BASE-TO-BASE SPACING OF 0.65 INCHES (17mm) MINIMUM, MEASURED BETWEEN THE MOST ADJACENT DOMES ON A SQUARE GRID.
3. DETECTABLE WARNINGS SHALL CONTRAST VISUALLY WITH ADJOINING SURFACES, EITHER LIGHT-ON-DARK, OR DARK-ON-LIGHT. THE MATERIALS USED TO PROVIDE CONTRAST SHALL BE AN INSTALLED PART OF THE WALKING SURFACE. DETECTABLE WARNINGS USED ON INTERIOR SURFACES SHALL DIFFER FROM ADJOINING WALKING SURFACES IN RESILIENCY OR SOUND-ON-GANE CONTACT.
4. ALL ACCESSIBLE ROUTE SIDEWALKS INTERSECTING ROADWAYS, DRIVEWAYS, OR OTHER VEHICULAR CROSSINGS REQUIRE DETECTABLE WARNINGS. DETECTABLE WARNING ZONES SHALL BE INSTALLED SIX (6) INCHES (OR THE HORIZONTAL THICKNESS OF THE ADJACENT CURB) FROM THE FLOW LINE OF THE CURB, EXTEND INTO THE SIDEWALK FOR A 24" DEPTH, AND COVER THE COMPLETE WIDTH OF THE SIDEWALK OR RAMP. DETECTABLE WARNING ZONES SHALL CONFORM TO THE SLOPE REQUIREMENTS OF THE RAMP, LANDING, OR ACCESSIBLE ROUTE AS DEFINED IN THE SPECIFIED DETAIL. DETECTABLE WARNINGS SHALL NOT BE INSTALLED IN FLARED SIDES, IF THE RAMP INCLUDES FLARED SIDES.
5. ALL LANDING AREAS SHALL BE 4 FEET WIDE BY 4 FEET LONG (MINIMUM DIMENSIONS), THE SLOPE OF THE LANDING AREA SHALL NOT EXCEED A 1:48 IN ANY DIRECTION.
6. ALL ACCESSIBLE ROUTE SLOPES ADJOINING THE LANDING AREA, EXCEPT THE CURB RAMP, SHALL NOT EXCEED A SLOPE OF 1:20 UNLESS OTHERWISE NOTED.




BARRIER FREE RAMP—ONSITE

N.T.S.



NTS

[illegible]

 **BH2M**

Berry, Huff, McDonald, Milligan Inc.
Engineers, Surveyors

28 Sans Street
Gorham, Maine 04038

Tel. (207) 839-2771
Fax (207) 839-8250

FOR
The Town Of Standish
175 Northeast Road
Standish, Maine 04084

ROADWAY & SIDEWALK DETAILS

ROUTE 25 & OAK HILL ROAD IMPROVEMENT PROJECTS

**ROUTE 25 AND OAK HILL ROAD
STANDISH, MAINE**

DESIGNED W. Pelkey	DATE Jan. 2012
DRAWN Dept.	SCALE As Noted
CHECKED L. Berry	JOB. NO. 11107

SHEET

8

REPRODUCTION OR REUSE OF THIS
DOCUMENT WITHOUT THE
EXPRESSED WRITTEN CONSENT
OF BH2M INC. IS PROHIBITED

1. STREET PAVING SHALL NOT BEGIN UNTIL SUBGRADE COMPACTION TESTS ARE TAKEN AND THE DESIGN ENGINEER APPROVES THE RESULTS.
2. PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION, THE CONTRACTOR SHALL PROVIDE THE TOWN WITH ATLEAST 24 HOURS ADVANCED NOTICE.
3. MAINTENANCE OF ONSITE DRAINAGE AND EROSION CONTROL FACILITIES DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. TEMPORARY EROSION CONTROL MEASURES SHALL BE PROVIDED BY THE CONTRACTOR DURING CONSTRUCTION AS IDENTIFIED ON THE EROSION CONTROL PLAN.
4. PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION, THE CONTRACTOR SHALL CONTACT ALL UTILITIES TO COORDINATE SCHEDULES.
5. PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION THE CONTRACTOR SHALL CONTACT THE DESIGN ENGINEER AND TOWN OF STANDISH.
6. ALL TRAFFIC CONTROL DEVICES, STRIPING AND SIGNAGE SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
7. PAVEMENT REMOVAL AND REPLACEMENT IN THE PUBLIC RIGHT OF WAY:

-
- 12" WIDE DRIVEWAY TYP.
- 3:1
- MIN. 15" COVER
- 15" DIA., 30' LONG MIN.
- CULVERT SHALL BE HDPE N12 OR EQUAL PIPE.
- RIPRAP D50=6" (MIN.)
- DITCH LINE
- MIRAF 700X FABRIC
- TYPICAL CULVERT SECTION
AT DRIVEWAY
NTS



NTS

- ## TRENCH DETAIL



SHEET

9

REPRODUCTION OR REUSE OF THIS
DOCUMENT WITHOUT THE
EXPRESSED WRITTEN CONSENT
OF BH2M INC. IS PROHIBITED